


RETAINING WALL FORMLINER GENERAL NOTES:

1. CONTRACTION JOINTS FOR THE FORMLINER WALL SHALL BE INSTALLED BY USE OF PREFORMED TEMPLATES INSTALLED PRIOR TO CONCRETE PLACEMENT. PREFORMED TEMPLATES MUST BE APPROVED BY THE CITY ENGINEER PRIOR TO USE.
2. FORMLINER PATTERN SHALL BE AS SHOWN ON THE CITY OF GARDNER APPROVED MATERIALS LIST.
3. PENETRATING STAIN AND CORRESPONDING COLORS SHALL BE AS SHOWN ON THE CITY OF GARDNER APPROVED MATERIALS LIST.
4. SUBMITTALS SHALL BE REQUIRED FOR ANY MATERIAL NOT SHOWN ON THE CITY OF GARDNER APPROVED MATERIALS LIST. CONTRACTOR SHALL ADHERE TO MANUFACTURER'S RECOMMENDATIONS FOR ALL APPROVED MATERIALS.
5. SEE SIDEWALK AND SIDEWALK WITH ABUTTING RETAINING WALL STANDARD DETAILS FOR ADDITIONAL REQUIREMENTS.

 <p>GARDNER KANSAS <i>Blazing New Trails</i></p>	<p><i>APPROVED</i></p> <p><u>TRM</u> <i>CITY ENGINEER</i></p> <p><u>5-25-22</u> <i>DATE</i></p>	<p><i>REVISED</i></p> <p>_____</p> <p>_____</p> <p>_____</p>	<p style="text-align: center;">RETAINING WALL FORMLINER (PAGE 2)</p>	<p>STANDARD DETAIL</p> <p style="text-align: center;">21-9C</p>
--	---	--	---	---